KADUR DIVISION.

ADVERTISEMENTS.

The 31st December 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 30th January 1889, for restoring the Gangenahalli Tank, Registered No. 718, Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Abstract.

Items of Work.	Per.	Quantity.	Rate.
Bund.—			
Earthwork including watering and tamping	C. Yd.	2,700	
Rough stone work (new)	do	1,470	
Rough stone work (old)	do	200	
Grade stones as per standard design	Each	48	
Bench Mark stones	do	2	
Registered No. stone..	do	1	
Gauge stones	do	3	
Left Kodi, 200 *feet long.*—			
Rough stone work (new)	C. Yd.	374	
Do Do (old)	do	429	
Excavation in soft rocky soil	do	104	
Burnt brick in surki mortar	C. Ft.	3,125	
Burnt stone slabs including fixing, &c.	S. Ft.	460	
Plastering in surki mortar	Sqr.	4·98	
Right Kodi, 200 *feet long*—			
Rough stone work (new)	C. Yd.	39	
Earthwork excavation in rocky soil	do	75	
Chipping the top surface of the rock .. .	do	20	
Burnt brick in surki mortar	C. Ft.	5,435	
Burnt stone slabs including dressing and fixing in mortar ..	S. Ft.	497	
Plastering in surki mortar	Sqr.	25·62	
Sluice No. I.—			
Building a masonry sluice	R. Ft.	64	
Sluice No. II.—			
Do do do	do	52	

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Gangenahalli Tank, Registered No. 718, Kadur Taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.